Comparative Statement

BBMP/2019-20/BD/WORK_INDENT38068

Balance works to Hoysala stadium and construction of Samudaya Bhavana at judicial layout in ward no.04

SNo	Item Name	Unit	Estimate Quantity	Estimate Rate	Total Amount	H V ONKARAPPA		MURTHY C N S (MURTHY C N S)	
						Quoted Rate	Total Amount	Quoted Rate	Total Amount
1	Supply and fixing of single skin kalzip roofing systems of 65/400, 0.9mm thick Aluminium standing seam roof sheets. The sheets comprise of Profiled sheeting of Aluminium self-supported standing seam roof system manufactured from Aluminium alloy AA 3004, minimum material thickness of 0.9mm and PVDF finishing RAL 9006 on the exposed surface with ST clips and necessary accessories. Structure: (i) Supplying, cutting, bending and fabricating hot rolled plates, sag rods, brackings and connection bolts to form a column, truss with base plates and purlins. (ii) Erection of the above truss work structure at required height. (iii) Providing and applying one coat of red oxide primer and two coats of synthetic enamel paint. The scope of work includes a) Design, Engineering, Fabrication and erection of steel structure, roof sheeting and facade system. b) Supply and installation of flashing, capping, screws and all other necessary accessories.	Sqm	333.00	15025.00	5003325.00	16512.00	5498496.00	17000.00	5661000.00
2	Removing and resetting footpath slab (P.no.270,I no.37.56 of P&IWTD SR 2018/19)	Sqm	660.00	212.76	140421.60	234.00	154440.00	250.00	165000.00
3	KSRRB 300-1. Earth work excavation by manual means in Ordinary Soil soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.MORTH chapter 3. (P No. 143/ Item No. 19.1/PWD SR 2018-19)	Cum	264.75	140.40	37170.90	154.00	40771.50	175.00	46331.25
4	Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting ,including form work,curing,including cost of alll materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc ,copmplete. (Data Rate)	Sqm	198.00	2337.00	462726.00	2568.00	508464.00	2700.00	534600.00
5	b)Providing and laying in position reinforced cement concrete of Design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70 cum and fine aggregtes @ 0.47cum, with super plasticisers @ 3 liters confirming to is 9103-1999 reafirmed-2008 at machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedastals, retaining walls, return walls, walls (any thickness) including attached pilasters, columnspillars, posts, struts, buttresses, bed blocks, anchor blocks & plinths etc., including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications.(P.No.14, I.No. 4.10 of PWD SR 2018-19)	Cum	2.23	6276.96	13997.62	6898.00	15382.54	6950.00	15498.50

SNo	Item Name	Unit	Estimate Quantity	Estimate Rate	Total Amount	H V ONKARAPPA		MURTHY C N S (MURTHY C N S)	
						Quoted Rate	Total Amount	Quoted Rate	Total Amount
6	Providing T.M.T. steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking, placing in position, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.(P.No.18, I.No. 4.46.2 of PWD SR 2018-19)	MT	0.48	76643.28	36788.77	84230.00	40430.40	85000.00	40800.00
7	Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, post and struts, square rectangular polygon in plan including cost of all materials, labour complete as per specifications.(P.No.16, I.No.4.32of PWD SR 2018-19)	Sqm	23.76	492.48	11701.32	541.00	12854.16	560.00	13305.60
8	KSRB 4-6.2 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for suspended floors, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specificaitons for heights more than 3.50m from ground level. - 0 to 5 mtrs. Specification No. KBS 4.6.2 (P.No.16, I.No.4.29 of PWD SR 2018-19)	Sqm	10.29	432.00	4445.28	474.00	4877.46	500.00	5145.00
9	KSRB 2-4 : Refilling available earth around pipe lines, cables in layers not exceeding 20 cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. zand lift upto 1.5m. Including cost of all labour complete as per specifications allow 60% of rate considered under item KSRB 2.3 (P.No.7, I.No.2.11 of PWD SR 2018-19)	Cum	49.70	130.68	6494.80	143.00	7107.10	160.00	7952.00
10	KSRB 4-1.6 ; Providing and laying in position plain cement concrete of Mix 1:2:4 with OPC @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregtes @ 0.53cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No.13, I.No.4.6 of PWD SR 2018-19)	Cum	299.07	5855.76	1751282.14	6435.00	1924515.45	6550.00	1958908.50
11	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum, with superplastisiser @3lts confirming to IS 9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintles, retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications.(P.No.14, I.No.4.11 of PWD SR 2018-19)	Cum	1.80	6111.72	11001.10	6716.00	12088.80	6850.00	12330.00

SNo	Item Name	Unit	Estimate Quantity	Estimate Rate	Total Amount	H V ONKARAPPA		MURTHY C N S (MURTHY C N S)	
						Quoted Rate	Total Amount	Quoted Rate	Total Amou
12	KSRB 14.6-2 :Providing and laying heavy duty cobble stones 75mm thick interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM of machineries complete as per specifications. Specification No. KBS (P.No. 103, I.No. 14.7 of CSR 2018-19)	Sqm	75.00	1198.80	89910.00	1317.00	98775.00	1400.00	105000.00
13	KSRB 5-11 : Providing and constructing load bearing wall with solid concrete blocks of size 400x200x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 5.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications. KBS No.5.4 (P.No.27, I.No.5.26.1 of PWD SR 2018-19)	Sqm	193.50	1038.96	201038.76	1141.00	220783.50	1200.00	232200.00
14	KSRB 6.1: Providing and constructing burnt brick masonry for basement and superstructure with approved quality of non-modular bricks of standard size of class designation 3.5 Newton per sqm with cement mortar 1:8 including cost of materials, labour charges, scaffolding, curing complete as per specifications. Specification No. KBS 6.2 (P.No.29, I.No.6.2 of PWD SR 2018-19)	Cum	19.53	6613.92	129169.86	7268.00	141944.04	7350.00	143545.50
15	KSRB 12-6.1 : Providing 20mm square M.S footrest and fixing in manhole with M 10 cement concrete block of 20x20x10cms, using 20mm and down size metal of size including cost of materials, labour charges, curing complete as per specifications. Specification No. KBS 12.4.6 (P.No.75, I.No.11.44 of PWD SR 2018-19)	No	10.00	298.08	2980.80	327.00	3270.00	350.00	3500.00
16	KSRB15-3.10 : Providing 20mm thick cement plaster in single coat with cement mortar 1:3, to stone masonry & concrete surface including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.(P.No.115, I.No.15.9 of PWD SR 2018-19)	Sqm	746.48	227.88	170107.86	250.00	186620.00	275.00	205282.00
17	KSRB 15.10.1 : Providing white washing to new wall surface in two coats with lime of approved quality, to give an even shade including cost of materials, labour, complete as per specifications.(P.No.117, I.No.15.38 of PWD SR 2018-19)	Sqm	507.68	12.96	6579.63	14.00	7107.52	16.00	8122.88
18	KSRB 15-15.3 : Providing and applying painting in one coat with plastic emulsion paint of approved brand and manufacture on wall surface to give an even approved shade after throughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications.(P.No.120, I.No.15.52.1 of PWD SR 2018-19)	Sqm	961.64	60.48	58160.13	66.00	63468.40	75.00	72123.18

SNo	Item Name	Unit	Estimate Quantity	Estimate Rate	Total Amount	H V ONKARAPPA		MURTHY C N S (MURTHY C N S)	
						Quoted Rate	Total Amount	Quoted Rate	Total Amount
19	KSRB 13-11.1 : Providing and placing on terrace, polyethylene water storage tanks with manhole lid and suitable locking arrangements, making holes of suitable diameter for inlet, outlet and over flow pipes, including cost of all materials, labour, transport charges, HOM of equipments and testing complete as per specifications. (For 1000 litre capacity) Specification No. KBS 13.22 (P.No.96, I.No.13.78 of PWD SR 2018-19)	No	2.00	7374.24	14748.48	8104.00	16208.00	8200.00	16400.00
20	KSRB 7.9: Providing and fixing M.S Grill work for windows and ventilators using M.S flats or M.S fsquare rods or combination of M.S flat and square rods as per approved deisgn, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materail, fixtures, labour and HOM of machinery complete as per specification. Specification No:KBS 7.12 (P.No:34 Items No:7.9 of PWD SR 2018-19)	kg	5212.20	102.60	534771.72	113.00	588978.60	125.00	651525.00
21	Providing and fixing M.S.Grill over existing compound wall as per Chief Architect drawing No. 12686, using 16mm x 16mm M.S.Square rod at 150mm c/c spacing and 6mm x 40mm M.S. flats at horizontal and 6mm x12mm M.S. flat for ornamental design and providing shop edge design at the vertex of every vertical rods, including welding, grinding wherever necessary. All the steel surface should be thoroughly cleaned free of rust and painted with anti corrosive paint (shop paint) etc., complete. The work includes cost of all materials, labour charges for all items of work, hire charges for welding, cutting and grinding equipment, and electricity charges, etc., complete as per specification. (P.No.44, I.No.7.36 of PWD SR 2018-19)	Sqm	150.00	5798.52	869778.00	6372.00	955800.00	6450.00	967500.00
22	KSRB 9.4-4 : Providing WHITE Sal wood frames of doors, windows, clerestory windows, ventilators and other frames, wrought, framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, HOM of machineries complete as per specifications. Specification No. KBS 9.33. (P.No.53, I.No.9.13 of PWD SR 2018-19)	Cum	0.25	65391.84	16217.18	71864.00	17822.27	72150.00	17893.20
23	KSRB 9-7.3 :Providing and fixing in position fully panelled Mathi/ Nandi wood shutters for doors, styles and rails of 30mm. thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries complete as per specifications. (excluding cost of fixtures) Specification No. KBS 9.34 (P.No.54, I.No.9.22 of PWD SR 2018-19)	Sqm	7.56	4122.36	31165.04	4530.00	34246.80	4650.00	35154.00
24	KSRB 15-17.3 : Applying priming coat over new wood surface and / or wood based surface after brushing with aluminium paint primer, water resistant including preparing the surface after thoroughly cleaning oil, grease, dirt and foreign matter, sand papering and knotting ready mix paint including cost of materials, labour, complete as per specifications.(P.No.121, I.No.15.57 of PWD SR 2018-19)	Sqm	15.12	45.36	685.84	50.00	756.00	60.00	907.20

Comparative Statement

SNo	Item Name	Unit	Estimate Quantity	Estimate Rate	Total Amount	H V ONKARAPPA		MURTHY C N S (MURTHY C N S)	
						Quoted Rate	Total Amount	Quoted Rate	Total Amount
25	KSRB 15-17.19: Providing and applying painting one coat (excluding priming coat) on previously painted wood surface and / or wood based surface with black japan paint to give an even shade after cleaning the surface of all dirt, dust and foreign matter, including cost of materials, labour, complete as per specifications.(P.No.123, I.No.15.71 of PWD SR 2018-19)	Sqm	15.12	60.48	914.46	66.00	997.92	75.00	1134.00
26	KSRB 15-17.20: Applying additional one coat (excluding priming coat) on previously painted wood surface and / or wood based surface with black japan paint to give an even shade after cleaning the surface of all dirt, dust and foreign matter, including cost of materials, labour, complete as per specifications.(P.No.123, I.No.15.72 of PWD SR 2018-19)	Sqm	15.12	54.00	816.48	60.00	907.20	75.00	1134.00
27	Providing and fixing in position in cement concrete 1:3:6 Steel glazed windows and Ventilators side hung/top hung 2/3 openable 1/3 fixed as per approved drawings using Z angles of 25x33x3mm, weighing 1.419kg/m both for outer and inner frames and central mullion section of size 25x46x3 mm, weighing 2.28kg/m all duly providing T section 19x19x3 mm weighing 0.839kg/m for glazing of windows, not more than 34 cms, C to C including providing and fixing 4mm, thick reeded glass with teakwood beading of required size, all steel sections should confirm to I.S. 7452:1990, 4nos. of holdfasts of approved size, section should be cut to length welded and grinded electrically subdividing frames of unit shall be tenoneed and revetted into the frames electrically. All the steel surface shall be throughly cleaned free of rust and painted with one coat of anti-corrosive paint and finishing two coats of ready mix paint of approved colour and make including cost of materials, fixtures, labour charges and HOM of machinery complete as per specifications.(P.No.34, I.No.7.8 of PWD SR 2018-19)	Sqm	2.88	3594.24	10351.41	3949.00	11373.12	4050.00	11664.00
28	Providing and fixing 12.5mm to 25 mm expanded metal work of 14 gauge with Mathi or Nandi wood patties of 50 mm x 12 mm size, including two coats approved paint etc., complete. (Including cost of screws). with weld mesh 75 mm X 25 mm 6G X 10G.(P.No.270, I.No.37.55 of PWD SR 2018-19)	Sqm	386.40	1601.64	618873.70	1760.00	680064.00	1850.00	714840.00
29	Providing and fixing 4mm thick glass panes to steel windows including T.W. beading of 10 mm thick and 2 coats of approved paints (P.No.267, I.No.37.16 of PWD SR 2018-19)	Sqm	56.40	855.36	48242.30	940.00	53016.00	975.00	54990.00
30	KSRB 15-18.1 : Applying red lead ready mix priming coat over new steel or other metal surface including preparing the surface after throughly cleaning oil, grease, dirt and other foreign matter, and scoured with wire brushes, fine steel wool, sand papers including cost of materials, labour, complete as per specifications..(P.No.123, I.No.15.73 of PWD SR 2018-19)	Sqm	12.00	44.28	531.36	48.00	576.00	55.00	660.00

SNo	Item Name	Unit	Estimate Quantity	Estimate Rate	Total Amount	H V ONKARAPPA		MURTHY C N S (MURTHY C N S)	
						Quoted Rate	Total Amount	Quoted Rate	Total Amount
31	Providing and laying plat form using prepolished, water cut / gang saw 40mm thick telephonic Black Granite. laid on existing vertical -supports and fixing in CM 1:3 proportion. Including cutting to required shape, pattern with paper joints, including full rounding for nosing, finished with cement mortar, pointed with colour pigments to match the colour of slab making through jointing with sealant, making holes 25mm x 12mm grooves in joints including curing. (P.No. 110, I.No. 14.52 of PWD SR 2018-19)	Sqm	67.00	3807.00	255069.00	4183.00	280261.00	4250.00	284750.00
32	Supplying and fixing M.S. Rectangular poles made out of 2 equal angles of 65x65x6 mm welded together and fixed in CC (1:2:4) WITH 2 NOS 16mm dia M.S. hold fast rods each of length 25 cms. Including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead lifts and as per the directions of the Engineerin - charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete) (P.No. 266, I.No. 37.2 of PWD SR 2018-19)	Mtr	120.00	927.72	111326.40	1018.00	122160.00	1100.00	132000.00
33	Providing chain link fencing 50mm size of 8 guage properly stretched between existing rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the Engineer-in-charge of work including two coats of approved quality paint over one coat of shop paint (P.No. 266, I.No. 37.3 of PWD SR 2018-19)	Sqm	180.00	772.20	138996.00	848.00	152640.00	860.00	154800.00
34	Providing & Fixing Name board (Lump Sum)	No	3.00	166666.67	500000.01	183166.00	549498.00	186000.00	558000.00
35	Providing Dust Bins (MR)	No	30.00	5000.00	150000.00	5495.00	164850.00	5500.00	165000.00
36	LED Street light/Flood Light. Supply of LED Streetlight with pressure die cast aluminum housing body with optimal heat sink for better thermal dissipation. Diffuser with Injection moulded & is made of polycarbonate material with high transmission index, delivering superior light output. Rated life Burning Hrs. 50000 hr. @ Lumen Maintenance of 70%. CCT > 5500K, IP 66 optical and electrical compartment & impact resistance of complete luminaire > IK08. Power Factor >0.9 with mains Current should not be greater than 0.1A to 0.7A & Surge Protection- Min 4 KV along with Over voltage/Overload, short circuit/ miswiring protection. Compatible for pole mounting with outer dia of 40mm to 50mm. Universal Voltage driver to operate wide voltage range from 100V to 270V 50/60Hz application. Over load & Short circuit protection ensures reliable operation in spite of problem in output side. Compliance to IS 10322/IEC 60598, LM 79 & LM 80 Adherence with RoHS. UL approved MCPCB. Top access street light with single screw to ensure ease of maintenance at the sight site location with minimized minimal tools.LED Light fixture with .....W System Power consumption. LED Efficiency>130lm/w at 1W & Fixture	No	20.00	43000.00	860000.00	47257.00	945140.00	48250.00	965000.00

SNo	Item Name	Unit	Estimate Quantity	Estimate Rate	Total Amount	H V ONKARAPPA		MURTHY C N S (MURTHY C N S)	
						Quoted Rate	Total Amount	Quoted Rate	Total Amount
37	LED Street light/Flood Light. Supply of LED Streetlight with pressure die cast aluminum housing body with optimal heat sink for better thermal dissipation. Diffuser with Injection moulded & is made of polycarbonate material with high transmission index, delivering superior light output. Rated life Burning Hrs. 50000 hr. @ Lumen Maintenance of 70%. CCT > 5500K, IP 66 optical and electrical compartment & impact resistance of complete luminaire > IK08. Power Factor >0.9 with mains Current should not be greater than 0.1A to 0.7A & Surge Protection- Min 4 KV along with Over voltage/Overload, short circuit/ miswiring protection. Compatible for pole mounting with outer dia of 40mm to 50mm. Universal Voltage driver to operate wide voltage range from 100V to 270V 50/60Hz application. Over load & Short circuit protection ensures reliable operation in spite of problem in output side. Compliance to IS 10322/IEC 60598, LM 79 & LM 80 Adherence with RoHS. UL approved MCPCB. Top access street light with single screw to ensure ease of maintenance at the sight site location with minimized minimal tools.LED Light fixture with .....W System Power consumption. LED Efficiency>130lm/w at 1W & Fixture	No	70.00	54000.00	3780000.00	59346.00	4154220.00	60100.00	4207000.00
38	Supplying of LED Floodlight/High Baylight with .....W System Power consumption pressure die cast aluminum housing with powder coating with IP 65 protection. 1, 200-275V voltage with electronic Driver, PF>0.9, should meet ANSI 2G Vibration test, Compliance to UL/CE with Class I. System rating shall be 50K hrs. @ Lumen maintenance of 70%, system efficacy > 80lm/w. Over load & Short circuit protection ensures reliable operation in spite of problem in output side. Compliance to IS 10322/IEC 60598, LM 79 & LM 80 Adherence with RoHS. UL approved MCPCB. Top access street light with single screw to ensure ease of maintenance at the sight site location with minimized minimal tools. LED Light fixture with .....W System Power consumption. LED Efficiency>130lm/w at 1W & Fixture Efficiency >80lm/w with nominal CRI >75. Luminaire manufacturer should have in-house facility accredited by NABL/CPRI & any Government certified agency & Design & Development facility certified by ISO 9001:2008. Housing with supplier word mark /name shall be Engraved / Embossing on the die cast housing/ Body part. Warranty of 5 Years against any manufacturing defect working under standard electrical	No	40.00	23577.00	943080.00	25911.00	1036440.00	26500.00	1060000.00

SNo	Item Name	Unit	Estimate Quantity	Estimate Rate	Total Amount	H V ONKARAPPA		MURTHY C N S (MURTHY C N S)	
						Quoted Rate	Total Amount	Quoted Rate	Total Amount
39	Supply of 2'x2' LED recessed luminaire with ...Watts system wattage. Housing shall be with pressure die cast aluminum alloy with corrosion proof resistant polyester power coated. Driver operates with voltage range from 100V to 270V 50/60 Hz with short circuit, overload & mis-wiring protection. Lumen Maintenance of 70% at 50000 Hrs. Injection moulded poly carbonate diffuser for better mechanical stability, light transmission & avoid pot hole effect. Junction temperature shall be < 70 degree Celsius. Driver is on constant current driver @ 0.06A with PF > 0.92 with line voltage @ 220-240V @ 50/60Hz, driver efficiency > 85% & THD<15%. LED Efficiency > 130 lm/W at 1W & Fixture Efficiency >75lm/w with CRI > 75 with injection moulded Polycarbonate lens with < 80mm depth. 5 years Warranty against any manufacturing defect working under standard electrical condition LED modular down light 2'x2'-36 watts SR No:26/4.33.2	No	4.00	8242.00	32968.00	9057.00	36228.00	9250.00	37000.00
40	Supply of 2'x2' LED recessed luminaire with ...Watts system wattage. Housing shall be with pressure die cast aluminum alloy with corrosion proof resistant polyester power coated. Driver operates with voltage range from 100V to 270V 50/60 Hz with short circuit, overload & mis-wiring protection. Lumen Maintenance of 70% at 50000 Hrs. Injection moulded poly carbonate diffuser for better mechanical stability, light transmission & avoid pot hole effect. Junction temperature shall be < 70 degree Celsius. Driver is on constant current driver @ 0.06A with PF > 0.92 with line voltage @ 220-240V @ 50/60Hz, driver efficiency > 85% & THD<15%. LED Efficiency > 130 lm/W at 1W & Fixture Efficiency >75lm/w with CRI > 75 with injection moulded Polycarbonate lens with < 80mm depth. 5 years Warranty against any manufacturing defect working under standard electrical condition LED modular down light 2'x2'-55 watts SR No:26/4.33.3	No	2.00	9373.00	18746.00	10300.00	20600.00	10500.00	21000.00
41	Fabricating, supplying and erecting swaged tubular pole of height ...Mtr having three sections, and providing two coats of red oxide paint and finished with two coats of enameled paint of approved quality and colour and M.S. base plate of suitable size welded at the bottom of the pole(as per IS) and 40mm dia GI / flexible PVC pipe of 1 mtr length fitted to the heavy gauge polycarbonate control box including 5way connector of size 167x125x82mm for 7.5M pole/200x160x98mm for remaining length of pole with front opening cover, with locking arrangements and suitable capacity MCB / DP switch, The pole shall be erected in cement concrete work (1:2:4) including excavation and refilling of planting depth of the pole to the ground level and the coping CC shall be up to 0.6M above ground level as per IS 2713 - 7. Erection of heavy duty pole on Footpath / median 10Mt (5Mt Hb,165.1mm dia 4.85mm thick x3M Hm, 139.7mm dia 4.50mm thick x 2M Ht,114.3mm dia 3.65mm thick) as per IS 410 SP 47 SR No:34/5.13.1.2	No	4.00	19000.00	76000.00	20881.00	83524.00	21250.00	85000.00

SNo	Item Name	Unit	Estimate Quantity	Estimate Rate	Total Amount	H V ONKARAPPA		MURTHY C N S (MURTHY C N S)	
						Quoted Rate	Total Amount	Quoted Rate	Total Amou
42	Supplying and fixing angle iron frame work fabricated out of M.S. angle iron.. and M.S. flat ... with bolts, washers etc., and painted with 2 coats of red oxide and then two coats of approved paint.40x40x6mm SR No:49/6.39.1	No	150.00	263.00	39450.00	289.00	43350.00	300.00	45000.00
43	Fabricating supplying and mounting MS box made out ... SWG suitable for floor / wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 2 coats of red oxide primer paint and finally finished with approved colour enameled metal paint etc., complete.16SWG SR No:49/6.40.2	Sqcm	150000.00	0.33	49500.00	0.36	54000.00	0.38	57000.00
44	Supplying and fixing Moulded Case Circuit Breaker (MCCB) over the existing wood/panel board using necessary screws, bolts, nuts and wiring complete. Protection of Overload and Short circuit with thermal Magnetic/Micro processor release and Earth Fault as per IS-13947. (Icu = Ics) FOUR POLE100Amps 25kA.SR No:46/6.13.B.6	No	2.00	5809.00	11618.00	6384.00	12768.00	6450.00	12900.00
45	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898.5-32Amps SP SR No:47/6.16.1	No	20.00	418.00	8360.00	459.00	9180.00	460.00	9200.00
46	Supplying of 1.1 KV LT UG cable having aluminum conductor PVC insulated, extruded inner sheathed, galvanized, steel strip (except 2CX10Sq.mm wire armoured) confirming to IS-3975:1990 (No. of Strip indicated in GTP) & extruded PVC outer sheathed armoured cable with specified IS-1554 Part-1:1988 & confirming to GTP of GROUP-A. 4 core 16 sqmm SR No:55/7.4.5	Mtrs	1100.00	165.50	182050.00	182.00	200200.00	200.00	220000.00
47	Supplying of 1.1 KV LT UG cable having aluminum conductor PVC insulated, extruded inner sheathed, galvanized, steel strip (except 2CX10Sq.mm wire armoured) confirming to IS-3975:1990 (No. of Strip indicated in GTP) & extruded PVC outer sheathed armoured cable with specified IS-1554 Part-1:1988 & confirming to GTP of GROUP-A. 3.5 core 35 sqmm SR No:55/7.4.6	Mtrs	250.00	204.00	51000.00	224.00	56000.00	250.00	62500.00
48	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required.In existing trench/duct. 6 sqmm to 16 sqmm SR No:61/7.8.1	Mtrs	1100.00	10.80	11880.00	11.00	12100.00	15.00	16500.00
49	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required.In existing trench/duct. 25 sqmm to 75 sqmm SR No:61/7.8.2	Mtrs	250.00	16.20	4050.00	17.00	4250.00	25.00	6250.00
50	Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete.(As per Civil SR KSRB I-2, P-7)In soil (ordinary) SR No:61/7.9.1	Mtrs	200.00	78.00	15600.00	85.00	17000.00	100.00	20000.00

SNo	Item Name	Unit	Estimate Quantity	Estimate Rate	Total Amount	H V ONKARAPPA		MURTHY C N S (MURTHY C N S)	
						Quoted Rate	Total Amount	Quoted Rate	Total Amount
51	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand Copper conductor single core wire in open or concealed system of wiring as per IS-694:1990 & confirming to GTP of GROUP -B. 1)1 sqmm.SR No:8/2.6.1	Mtrs	100.00	10.75	1075.00	11.00	1100.00	15.00	1500.00
52	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand Copper conductor single core wire in open or concealed system of wiring as per IS-694:1990 & confirming to GTP of GROUP -B. 1.5 sqmm SR No:8/2.6.2	Mtrs	600.00	15.90	9540.00	17.00	10200.00	25.00	15000.00
53	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand Copper conductor single core wire in open or concealed system of wiring as per IS-694:1990 & confirming to GTP of GROUP -B. 2.5 sqmm SR No:8/2.6.3	Mtrs	300.00	24.90	7470.00	27.00	8100.00	35.00	10500.00
54	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand Copper conductor single core wire in open or concealed system of wiring as per IS-694:1990 & confirming to GTP of GROUP -B..4 sqmm SR No:8/2.6.4	Mtrs	200.00	36.30	7260.00	40.00	8000.00	50.00	10000.00
55	Supplying heavy gauge PVC conduit pipe .....dia .....mm thick confirming to IS 2509 with suitable size bends, junction boxes, adhesive paste etc., and fixing using inverted wood plugs in case of RCC ceiling and RCC wall / stone structure or rawl plugs in case of brick walls and cement plastering the damaged portion using heavy gauge saddles at an interval of 700mm using NF screws.19/20mm dia 2mm thick SR No:2/1.1.1	Mtrs	300.00	54.00	16200.00	59.00	17700.00	65.00	19500.00
56	Supplying and fixing of class A (medium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV.40mm SR No:62/7.1	Mtrs	30.00	345.00	10350.00	389.00	11670.00	405.00	12150.00
57	Supply and Installation / Fixing / Provision of Pole box with HRC Fuse / MCB provision and suitable connector / terminal for 3 Ph / 1 Ph connections with Loop-In & Loop-Out terminals for 10 Sqmm / 25 Sqmm 3.5 C Al/Ar / Cu/Ar Cable and branch out 2.5 Sqmm 2 core Al/Cu PVC Insulated cable, enclosed in a Thermoplastic, Polystyrene enclosure, which should be shock proof, safe, IP65(Weather Proof), rust proof, dust proof, water proof having Internally Embedded Gasket with provision for cable entry through IP65 Thermoplastic, polyamide glands and/or grommets.200mmx200mmx98mm SR No:58/6.41.1	Mtrs	75.00	2178.00	163350.00	2393.00	179475.00	2450.00	183750.00
58	Providing and Supplying Submersible single Phase 2.0 HP /1.5 KW 30 Stage Capacity Company for ATALANTA / SUGUNA / CRI / KIRLOSKAR / OTHER EQUIVALENT PUMPS.(KPWD SR 2018-19, P.No:XLIII, Sl.No.:17)	No	1.00	22237.20	22237.20	24438.00	24438.00	75500.00	75500.00
59	Electrification & Automatic On/Off Sensor system	No	1.00	60000.00	60000.00	65940.00	65940.00	66800.00	66800.00
	Total Summary Amount				17821573.06		19583173.78		20218045.81
	% against Estimated Rate						9.88		13.45
	Total Bid Amount					19583173.78 (L1)		20218045.81 (L2)	

6/12/19